

**Notice to Prospective Bidders
Addendum Number 1**

Bid Documents for
REPLACEMENT OF EXISTING PLUMBING WASTE PIPE RISERS
Elm Park Towers
Worcester Housing Authority
Worcester, Massachusetts

Prospective bidders for the above project are hereby notified of administrative changes to the Bid Documents.

1. Clarification: General Contractor to provide and install access panels. Plumbing contractor to coordinate all locations with General Contractor.
2. Drawing P002 Typical Kitchen Sink Riser Clarification: All kitchen sink stacks shall be removed and replaced in their entirety.
3. Drawing P200: General Contractor to protect all computer equipment as needed for renovations in Training Room.
4. Drawings P200/P201: Intent of drawings is to replace waste stacks and immediate branch lines to plumbing fixtures within plumbing chases. Scope of work should be limited to plumbing chases where possible. Should additional waste arms, traps, closet flanges etc. need to be replaced upon inspection, they shall be replaced in accordance to the unit prices agreed upon in the contract.
5. Drawing P200/201: 3" waste stack located in Unit 206 shall be brought down independently of the So Vent system and tied into the sanitary system downstream of the last So Vent fitting in the first floor.
6. Drawing P201 Clarification: Removal and reinstallation of lightning protection shall be by the General Contractor. Installation by an Electrical Contractor shall not be required.
7. 09900 Painting Specification: Delete - Summary Section 1.05 Paragraph I Line 1 items C, D, E and H as these items will not be furnished on this project.
8. Drawing P100/P101/P200/P201/P201 Clarification: All cutting and patching shall be by the General Contractor.
9. All other times and dates stated in specifications and advertisement shall remain unchanged.

End of Addendum #1

All bidders are required to acknowledge addenda in the appropriate section of the bid documents. Failure to do so may result in rejection of the bid.