

THE COMMONWEALTH OF MASSACHUSETTS  
University of Massachusetts  
Procurement Dept.  
140 Hicks Way / 407 Goodell Building  
AMHERST, MA 01003

28 June 2011

**ADDENDUM #1**

**Contract #:** UMA11-52  
**Project #:** 09-00176000  
**Account #:** 138064  
**Project Title:** Morrill IV 434,434A, 438, 438A, 438B

The attention of bidders submitting proposals for the above subject project is called to the following addendum to the specifications and drawings. The items set forth herein, whether of omission, addition, substitution, or clarifications are all to be included in and form a part of the proposal submitted.

The number of this Addendum (1) must be entered in the appropriate space "**B. This bid includes addenda numbered (list all addenda) \_\_\_\_\_**" found on Page 51 – Form for General Bid, and/or Page 59 – Form for Sub-Bid "**B. This sub-bid includes addenda numbered (list all addenda) \_\_\_\_\_**".

- Item 1. Section 260001, Part 1.01 D, Reference Drawings Page 260001-1 Add contract drawings as follows  
E-1 Electrical Symbols and Electrical Demolition Plan  
E-2 Lighting and Power Plan  
E-3 Fire Alarm Plan
- Item 2. Section 114001 paragraph 2.02 Materials, sub paragraph E, page 11400107, change E to F. and add provide vacuum faucet at each work bench.
- Item 3. Section 114001 paragraph 2.02 Materials, page 11400107, add sub-paragraph G. as follows  
G. Ball Valves 4 required furnished and installed, air, gas, vacuum and water at both the Fume Hood and the Bio Cabinet
- Item 4. Section 011000 Summary, Paragraph 1.17 Cutting, Coring and Patching, Unless Otherwise Indicated, sub paragraph D. Performance add sub-paragraph 9 as follows

9. All cutting and patching of the existing roof for the installation of the new roof vents shall be done by a roofing contractor approved by the existing roof membrane manufacture to certify the existing roof warranty is still in effect.

Item 5. Drawing A-4 Interior Elevations; Elevation 4 Provide 3-2'-8" w x 2'-6" h open shelved cabinets and fillers.

Item 6. Drawing A-2, New Floor Plan, Microscope Room 436C on the wall separating 436C and Corridor 499 B furnish and install wall to wall glass sliding doors cabinets 2'-8" w x 2'-6" h hand require fillers at high of all wall cabinets.

\*\*\* End of Addendum # 1 \*\*\*

By: John O. Martin  
Director  
Procurement